

SAMPLE BID
Job Number: 20001
Extension By Phase

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- 01 Raceway, Fittings & Boxes ---								
1000	1/2" EMT	6,222	44.59	C	2,774.39	2.00	C	124.44
1001	3/4" EMT	3,594	69.15	C	2,485.25	2.25	C	80.87
1002	1" EMT	1,446	122.73	C	1,774.68	2.50	C	36.15
1004	1-1/2" EMT	55	244.10	C	134.26	3.00	C	1.65
1005	2" EMT	11	290.78	C	31.99	3.25	C	0.36
1007	3" EMT	528	583.26	C	3,079.61	5.00	C	26.40
1121	1/2" Steel Flex	2,941	52.39	C	1,540.79	1.53	C	45.00
1143	1/2" Liquidtight (metallic)	55	93.92	C	51.66	1.75	C	0.96
1144	3/4" Liquidtight (metallic)	35	127.73	C	44.71	1.75	C	0.61
1145	1" Liquidtight (metallic)	5	251.80	C	12.59	2.41	C	0.12
1341	1-1/2" EMT Elbow	3	467.27	C	14.02	0.26	E	0.78
1344	3" EMT Elbow	18	2,084.93	C	375.29	0.53	E	9.54
1436	1/2" Set Screw Steel Conn	534	22.76	C	121.54	0.04	E	21.36
1437	3/4" Set Screw Steel Conn	222	31.73	C	70.44	0.05	E	11.10
1440	1-1/2" Set Screw Steel Conn	8	169.22	C	13.54	0.11	E	0.88
1441	2" Set Screw Steel Conn	2	311.79	C	6.24	0.14	E	0.28
1443	3" Set Screw Steel Conn	18	6.52	E	117.36	0.20	E	3.60
1476	1/2" Compression Steel Connector	32	76.09	C	24.35	0.10	E	3.20
1477	3/4" Compression Steel Connector	14	104.82	C	14.67	0.11	E	1.54
1478	1" Compression Steel Connector	70	195.80	C	137.06	0.13	E	9.10
1546	1/2" Set Screw Die Cast Cplg	123	21.68	C	26.67	0.02	E	2.46
1547	3/4" Set Screw Die Cast Cplg	6	35.71	C	2.14	0.02	E	0.12
1556	1/2" Set Screw Steel Cplg	401	26.96	C	107.97	0.04	E	16.02
1557	3/4" Set Screw Steel Cplg	7	42.82	C	2.78	0.05	E	0.33
1560	1-1/2" Set Screw Steel Cplg	9	192.03	C	16.32	0.10	E	0.85
1561	2" Set Screw Steel Cplg	0	256.48	C	0.26	0.11	E	0.01
1563	3" Set Screw Steel Cplg	71	675.76	C	478.44	0.13	E	9.20
1566	1/2" Compression Die Cast Cplg	46	57.15	C	26.29	0.08	E	3.68
1567	3/4" Compressin Die Cast Cplg	5	73.34	C	3.67	0.09	E	0.45
1576	1/2" Compression Steel Coupling	53	88.08	C	46.42	0.08	E	4.22
1577	3/4" Compression Steel Coupling	126	114.84	C	144.58	0.10	E	12.59
1578	1" Compression Steel Coupling	145	200.31	C	289.65	0.11	E	15.91
1599	3/4" Plastic Bushing	216	8.89	C	19.20	0.01	E	2.16
1602	1-1/2" Plastic Bushing	8	24.96	C	2.00	0.02	E	0.16
1603	2" Plastic Bushing	2	49.40	C	0.99	0.03	E	0.06
1605	3" Plastic Bushing	18	111.26	C	20.03	0.04	E	0.72
1878	1/2" Die Cast Screw-In Flex Conn	52	33.89	C	17.62	0.06	E	3.12
1885	1/2" Die-Cast Straight Squeeze Flex Conn	11	93.73	C	10.31	0.07	E	0.77
1910	1/2" Greenfield Conn 90D	11	416.11	C	45.77	0.11	E	1.21
1930	1/2" Seal-tite Conn (Str)	11	236.95	C	26.06	0.06	E	0.66
1931	3/4" Seal-tite Conn (Str)	7	329.37	C	23.06	0.08	E	0.56
1932	1" Seal-tite Conn (Str)	1	435.89	C	4.36	0.11	E	0.11
1951	1/2" Seal-tite Conn (90 Degree)	11	393.74	C	43.31	0.16	E	1.76
1952	3/4" Seal-tite Conn (90 Degree)	7	576.82	C	40.38	0.19	E	1.33
1953	1" Seal-tite Conn (90 Degeree)	1	1,101.83	C	11.02	0.24	E	0.24
2278	1/2" 1-Hole Strap	589	7.77	C	45.78	2.00	C	11.78
2279	3/4" 1-Hole Strap	230	11.86	C	27.31	2.00	C	4.61
2304	1/2" T-Bar Wire Conduit Clip	608	37.56	C	228.44	0.01	E	6.08
2305	3/4" T-Bar Wire Conduit Clip	7	39.34	C	2.83	0.02	E	0.14
2335	1/2" Unistrut Strap	66	44.03	C	29.00	3.94	C	2.60
2336	3/4" Unistrut Strap	157	45.75	C	72.00	4.38	C	6.89
2337	1" Unistrut Strap	181	51.24	C	92.62	5.25	C	9.49

* Target, Labor column 1

SAMPLE BID
Job Number: 20001
Extension By Phase

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2359	1-1/2" Conduit Hanger w/Bolt	7	80.20	C	5.51	11.00	C	0.76
2360	2" Conduit Hanger w/Bolt	0	99.48	C	0.12	8.75	C	0.01
2362	3" Conduit Hanger w/Bolt	66	154.88	C	102.22	13.13	C	8.67
2552	Hex Nut 3/8" Zinc Plated	466	30.48	C	142.04	0.20	C	0.93
2556	Flange Beam Clamp for 3/8" Thrd Rod	153	108.26	C	165.64	8.75	C	13.39
2560	3/16X3 Toggle Bolt	54	25.50	C	13.77	9.63	C	5.20
2571	4" Square Box (1/2 & 3/4 KO's)	202	124.73	C	251.95	0.16	E	32.32
2572	4" Square x 1-1/2" Deep Box w/bkt (1/2&3/4 KO's)	333	203.46	C	677.52	0.18	E	59.94
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	200	260.56	C	521.12	0.18	E	36.00
2576	4-11/16" Square Box Comb KO's	34	420.32	C	142.91	0.19	E	6.46
2577	4-11/16" Square Box w/brkt Comb KO's	12	377.06	C	45.25	0.22	E	2.64
2579	1G WP Bell Box-(3)1/2" Hubs	8	357.05	C	28.56	0.26	E	2.08
2592	4G Box	1	17.23	E	17.23	0.15	E	0.15
2702	11-1/2"-18-1/2" Bar Hanger w/clip	1	480.47	C	4.80	0.10	E	0.10
2726	4" Square-3/0 Plaster Ring-5/8"D	71	66.23	C	47.02	0.06	E	4.26
2731	4" Square-1G Plaster Ring-5/8"D	501	70.76	C	354.51	0.06	E	30.06
2736	4" Square-2G Plaster Ring-5/8"D	12	94.44	C	11.33	0.06	E	0.72
2759	4-11/16"-1G Plaster Ring-5/8"D	12	219.71	C	26.37	0.07	E	0.84
2779	4G Ring-3/4"D	1	1,081.32	C	10.81	0.07	E	0.07
5046	T-Bar Box Hanger	15	761.75	C	114.26	0.11	E	1.65
6420	12"x12"x10' Wireway-Nema 1	4	268.38	E	1,073.52	1.00	E	4.00
6438	12"x12" Wireway End	4	10.93	E	43.72	0.22	E	0.88
1234717	3/4" EMT LB Condulet w/Cover & Gasket	1	396.82	C	3.97	0.16	E	0.16
1234723	3" EMT LB Condulet w/Cover & Gasket	3	81.29	E	243.87	0.63	E	1.89
--- 01 Raceway, Fittings & Boxes Total ---					18,779.74			711.41
--- 02 Wire & Cable ---								
2787	#12 THHN CU Solid Wire	624	119.33	M	74.46	4.81	M	3.00
2790	#12 THHN CU Stranded Wire	40,142	121.74	M	4,886.88	4.81	M	193.08
2791	#10 THHN CU Stranded Wire	8,728	188.12	M	1,641.95	5.25	M	45.82
2792	#8 THHN CU Stranded Wire	282	303.98	M	85.72	5.47	M	1.54
2793	#6 THHN CU Stranded Wire	2,491	454.34	M	1,131.76	6.13	M	15.27
2797	#1 THHN CU Stranded Wire	780	1,500.09	M	1,170.07	9.63	M	7.51
2798	#1/0 THHN CU Stranded Wire	843	1,818.16	M	1,532.71	11.38	M	9.59
2800	#3/0 THHN CU Stranded Wire	124	2,804.74	M	347.79	14.88	M	1.85
2803	#300MCM THHN CU Stranded Wire	4,332	4,393.50	M	19,032.64	21.88	M	94.78
4367	#14-12-10 Wire Termination Labor	85	0.00	E	0.00	0.09	E	7.65
4368	#8-6 Wire Termination Labor	24	0.00	E	0.00	0.13	E	3.12
5045	Manufactured Fixture Whip	107	759.24	C	812.39	0.13	E	13.91
--- 02 Wire & Cable Total ---					30,716.37			397.12
--- 03 Distribution ---								
600	600A/3P 4WSN 240V HD FusSafety Sw-Nema3R	1	2,316.08	E	2,316.08	6.38	E	6.38
3143	30A/2P 3WSN 240V GD Fus Safety Sw-Nema 1	11	35.82	E	394.02	0.44	E	4.84
3161	30A/3P 4WSN 240V GD Fus Safety Sw-Nema3R	11	77.83	E	856.13	0.94	E	10.34
3162	60A/3P 4WSN 240V GD Fus Safety Sw-Nema3R	8	114.06	E	912.48	1.41	E	11.28
3284	20A 250V RK5 Time Delay Fuse	49	3.96	E	194.04	0.04	E	1.96
3286	30A 250V RK5 Time Delay Fuse	6	4.30	E	25.80	0.04	E	0.24
3290	50A 250V RK5 Time Delay Fuse	21	7.25	E	152.25	0.04	E	0.84
3291	60A 250V RK5 Time Delay Fuse	3	7.89	E	23.67	0.04	E	0.12
3643	3KVA 120/240Vx12/24V Sgl Phase Xfmr	1	234.00	E	234.00	3.28	E	3.28
DP	600A Distribution Board-Nema 1	1	QUOTE	2	0.00	11.75	E	11.75
LA	200 Amp Surf Panel-Nema 1	1	QUOTE	2	0.00	7.25	E	7.25

* Target, Labor column 1

SAMPLE BID
Job Number: 20001
Extension By Phase

Item #	Description	Quantity	Price U	Ext Price	Labor Hr U	Ext Lab Hr
LB-LC-LD	125 Amp Surf Panel-Nema 1	3	QUOTE 2	0.00	7.19 E	21.57
	--- 03 Distribution Total ---			5,108.47		79.85
--- 04 Light Fixtures & Lamps ---						
4990	T-Bar Box Hanger	95	761.75 C	723.66	0.11 E	10.45
4992	#10 Jack Chain	260	46.00 C	119.60	4.38 C	11.39
L-1	2'x4' Fluor Lay-In	5	QUOTE 1	0.00	0.39 E	1.95
L-11	Wall Bracket Fixture	11	QUOTE 1	0.00	0.35 E	3.85
L-5	Wall Bracket Fixture	8	QUOTE 1	0.00	0.35 E	2.80
L-6	Medium Recessed Incand Downlight	33	QUOTE 1	0.00	0.43 E	14.19
L1-E	2'x4' Fluor Lay-In	6	QUOTE 1	0.00	0.39 E	2.34
L10	Medium Recessed Incand Downlight	6	QUOTE 1	0.00	0.43 E	2.58
L12	Exit Fixture w/Batt Pack	29	QUOTE 1	0.00	0.50 E	14.50
L4	2'x4' Fluor Lay-In	8	QUOTE 1	0.00	0.39 E	3.12
L4-E	2'x4' Fluor Lay-In	7	QUOTE 1	0.00	0.39 E	2.73
L6E	Medium Recessed Incand Downlight	2	QUOTE 1	0.00	0.43 E	0.86
L7	4' Wrap-Around 2-Lamp	7	QUOTE 1	0.00	0.50 E	3.50
L7AE	4' Wrap-Around 2-Lamp	9	QUOTE 1	0.00	0.50 E	4.50
L8	1'x4' Surf Commercial Fluor	18	QUOTE 1	0.00	0.50 E	9.00
L8E	1'x4' Surf Commercial Fluor	8	QUOTE 1	0.00	0.50 E	4.00
L9	4' Wrap-Around 2-Lamp	24	QUOTE 1	0.00	0.50 E	12.00
LA	2'x4' Fluor Lay-In	3	QUOTE 1	0.00	0.39 E	1.17
LB	2'x4' Fluor Lay-In	5	QUOTE 1	0.00	0.39 E	1.95
LBE	2'x4' Fluor Lay-In	4	QUOTE 1	0.00	0.39 E	1.56
LC	2'x4' Fluor Lay-In	13	QUOTE 1	0.00	0.39 E	5.07
LCE	2'x4' Fluor Lay-In	13	QUOTE 1	0.00	0.39 E	5.07
LD	2'x4' Fluor Lay-In	7	QUOTE 1	0.00	0.39 E	2.73
LDE	2'x4' Fluor Lay-In	5	QUOTE 1	0.00	0.39 E	1.95
LE	2'x4' Fluor Lay-In	14	QUOTE 1	0.00	0.39 E	5.46
LEE	2'x4' Fluor Lay-In	1	QUOTE 1	0.00	0.39 E	0.39
LF	2'x4' Fluor Lay-In	8	QUOTE 1	0.00	0.39 E	3.12
LFE	2'x4' Fluor Lay-In	8	QUOTE 1	0.00	0.39 E	3.12
LG	Medium Recessed Incand Downlight	1	QUOTE 1	0.00	0.43 E	0.43
Z	Wall Bracket Fixture	5	QUOTE 1	0.00	0.35 E	1.75
	--- 04 Light Fixtures & Lamps Total ---			843.26		137.53
--- 05 Wiring Device & Covers ---						
4459	20A Spec Grade SP Switch	13	222.48 C	28.92	0.13 E	1.69
4483	20A Spec Grade 3-Way Switch	4	318.70 C	12.75	0.22 E	0.88
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	163	138.44 C	225.66	0.13 E	21.19
4518	20A/125V Spec Grade GFI Dup Rcpt (5-20R)	98	9.95 E	975.10	0.17 E	16.66
4657	SP 600W Fluor Rotary Dimmer w/Plt-120V	12	47.02 E	564.24	0.32 E	3.84
4672	1G Plastic Switch Plate	11	27.08 C	2.98	0.07 E	0.77
4673	1G Plastic Duplex Receptacle Plate	149	27.69 C	41.26	0.05 E	7.45
4679	1G Plastic Decora Plate	122	27.72 C	33.82	0.07 E	8.54
4680	2G Plastic Switch Plate	1	60.74 C	0.61	0.09 E	0.09
4681	2G Plastic Duplex Receptacle Plate	7	54.16 C	3.79	0.07 E	0.49
4683	2G Plastic Decora Plate	4	61.34 C	2.45	0.09 E	0.36
4690	4G Plastic Switch Plate	1	157.45 C	1.57	0.12 E	0.12
4701	1G SS Tel Plate	12	156.53 C	18.78	0.07 E	0.84
4771	1G WP In Use Cover	8	8.20 E	65.60	0.11 E	0.88
4790	4" Square Flat Blank Cover	147	46.38 C	68.18	0.06 E	8.82
4792	4-11/16" Square Blank Cover	34	371.40 C	126.28	0.07 E	2.38

* Target, Labor column 1

SAMPLE BID
Job Number: 20001
Extension By Phase

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
8261	Ground Screw with Bare Pigtail	8	916.90	M	7.34	1.00	C	0.08
22951	24 Volt DC Occupancy Sensor (Watt Stopper CX-100)	2	137.60	E	275.20	0.21	E	0.42
22952	IV Auto Wall Switch Occupancy Sensor (WS-120/277-	24	60.00	E	1,440.00	0.21	E	5.04
22953	Power Pack for Occupancy Sensor (Watt Stopper A27	2	62.16	E	124.32	0.21	E	0.42
123456	20A/125V WP GFI Dup Rcpt (5-20R)	8	13.66	E	109.28	0.17	E	1.36
--- 05 Wiring Device & Covers Total ---					4,128.13			82.32
--- 07 Misc ---								
2539	1/2" Roof Flashing	8	5.99	E	47.92	0.19	E	1.52
2540	3/4" Roof Flashing	8	5.99	E	47.92	0.19	E	1.52
2550	3/8" All Thread	446	55.95	C	249.54	5.50	C	24.53
3107	1/8" Poly Pull Line	2,213	5.80	M	12.83	1.75	M	3.87
6643	Unistrut (Shallow)	106	230.99	C	244.85	8.50	C	9.01
6644	Unistrut (Deep)	110	178.41	C	196.25	8.75	C	9.63
6650	Cut 12 Gauge 1-5/8x1-5/8 Channel (labor)	40	0.00	E	0.00	0.13	E	5.20
6651	1/4" Spring Nut	64	65.21	C	41.73	4.38	C	2.80
6839	Red Wirenuts	2,397	67.06	M	160.74	1.53	C	36.67
6841	Blue Wirenuts	24	507.50	M	12.18	2.63	C	0.63
8917	Ground Screw	35	7.30	C	2.56	0.01	E	0.35
8918	6X1/4" Pan Head Tapping Screw	172	2.36	C	4.06	0.01	E	1.72
10715	10-24X1-3/4" Round Hd Machine Scre	64	16.63	C	10.64	0.03	E	1.92
1234701	A/B Wall Mounted Occupancy Sensor	7	54.60	E	382.20	0.25	E	1.75
T0001	ATS	1	50.00	E	50.00	8.00	E	8.00
T0003	COMBO FLOOR BOX	1	550.00	E	550.00	8.00	E	8.00
T0004	WALL HEATER	1	125.00	E	125.00	2.00	E	2.00
T0005	floor scale	2	125.00	E	250.00	2.00	E	4.00
T0006	TC LCP	1	150.00	E	150.00	8.00	E	8.00
T0007	120V J-BOX	2	85.00	E	170.00	1.00	E	2.00
--- 07 Misc Total ---					2,708.42			133.12
--- 10 Voice/Data/Video ---								
19868	Plenum Cat 5 24gauge 4pair	1,200	2,074.05	M	2,488.86	7.70	M	9.24
--- 10 Voice/Data/Video Total ---					2,488.86			9.24
Job Total					64,773.25			1,550.59